संभागीय कार्यालय , नगरीय प्रशासन एवं विकास , सागर सम्भाग, सागर

SAGAR, दिनांक - 12.12.2024

क्रमांक/सं.प्र./तक.स्वी./नाली निर्माण/2024/ 1495

प्रति,

मुख्य नगर पालिका अधिकारी,
JATARA NAGAR PARISHAD,जिला:TIKAMGARH

विषय:- MINI HIGHMAST LIGHTING की तकनीकी स्वीकृति के सम्बंध में।

संदर्भ:- E-NOTIFICATION NUMBER PROJECT NUMBER PW137524016000

विषयान्तर्गत, सन्दर्भित पत्र से निकाय क्षेत्रान्तर्गत में MINI HIGHMAST LIGHTING निर्माण कार्यो के प्राक्कलनों का परीक्षण किया गया। निर्माण कार्य प्रारंभ करने के पूर्व शासकीय इंजीनियर कॉलेज से स्ट्रक्चरल डिज़ाईन कराकर उसका अनुमोदन इस कार्यालय से कराया जाना सुनिश्चित करे | मध्यप्रदेश नगर पालिका लेखा एवं वित्त नियम 2018 अनुसार पश्चात तकनीकी स्वीकृति प्रदान की जाती है .

क्र.	कार्य का नाम	मद	प्रभावशील एस.ओ.आर. का विवरण	तकनीकी स्वीकृति की राशि
1	MINI HIGHMAST LIGHTING	न.पा. निधि /अनुदान	UADD S.O.R 02.08.21	961710.62

शर्तः-

1. मध्यप्रदेश नगरपालिका (लेखा एवं वित्त) नियम के प्रावधान अनुसार कार्यवाही करना सुनिश्चित करे।
2. तथ्यो को छुपाकर निजी/अवैध कॉलोनी में निर्माण करने पर प्राप्त तकनीकी स्वीकृती स्वमेव ही निरस्त मानी जावेगी, जिसके लिए निकाय के मुख्य नगरपालिका अधिकारी पूर्णतः जवाबदार रहेंगे।
3. मध्यप्रदेश नगरपालिका (लेखा एवं वित्त) नियम 2018 के अनुरुप सक्षम स्वीकृती प्राप्त करना ,बयाना जमा , निष्पादन प्रतिभूति सुरक्षा जमा तथा निविदा प्रक्रिया आदि की कार्यवाही करना सुनिश्चित करे।
4. निर्माण कार्य स्वंय के अधिपत्य की भमि में ही किया जावे, अन्य विभाग की भूमि होने पर कार्य प्रारम्भ करने से पूर्व उसकी अनापत्ती अथवा हस्तांरण की कार्यवाही की जावे । निर्माण के दौरान खुदाई मे प्राप्त सामग्री का अधिक्तम उपेयोग किया जावे एवं स्थल पर वास्तविक रुप से सम्पन्न कार्यो का ही भुगतान किया जावे ।
5. भूमि विवाद की स्थिती में अथवा शासकीय विभाग द्वारा आपत्ती ली जाने पर प्राप्त तकनीकी स्वीकृति स्वतः ही निरस्त मानी जावेगी ।
6. बड़ी परियोजना, एकमुश्त प्रोजेक्ट, समान स्वरुप के कार्य को विभाजित कर, पृथक-पृथक ली गई प्राप्त तकनीकी स्वीकृती स्वतः निरस्त मानी जावेगी तथा इस तरह के कार्य को प्रस्तावित करने के लिए निकाय के मुख्य नगरपालिका अधिकारी जिम्मेदार रहेंगे।
7. निर्माण कार्य के दौरान सी.पी.डब्ल्यू.डी. स्पेसिफिकेशन एवं यू.ए.डी.डी. स्पेसिफिकेशन का पालन सुनिश्चित किया जावे ।
8. उक्त तकनीकी स्वीकृति मूल कार्य के लिए प्रदाय की जा रही है, रिवाईस्ड/सप्लीमेन्ट्री कार्यो के लिए नही। तथ्यो को छुपाने पर प्राप्त स्वीकृति निरस्त मानी जावेगी।
9. सी.पी.डब्ल्यू. डी. स्पेसिफिकेशन एवं यू.ए.डी.डी. स्पेसिफिकेशन का पालन सुनिश्चित किया जावे। निर्माण कार्यो मे प्रयुक्त निर्माण सामग्री/कॉक्रिट आदि का मान्यता प्राप्त प्रयोगशाला से निर्धारित आवृत्ति अनुसार परिक्षण कराया जावे । संतोषजनक परिक्षण परिणाम प्राप्त होन पर चलदेयको के भुगतान की कार्यवाही की जावे ।
10. मध्यप्रदेश नगरपालिका (लेखा एवं वित्त) नियम 2018 के अनुरुप सक्षम स्वीकृती प्राप्त करना ,बयाना जमा , निष्पादन प्रतिभूति सुरक्षा जमा तथा निविदा प्रक्रिया आदि की कार्यवाही करना सुनिश्चित करे ।
11. सीमेन्ट, कॉक्रींट एवं आर.सी.सी. नाली निर्माण में स्टील सेन्टरिंग का उपयोग किया जावे । कॉक्रीट मिक्सिंग के लिए मिक्सर मशीन तथा वाईब्रेटर का उपयोग अनिवार्यतः किया जावे ।
12. निर्माण कार्य स्वंय के अधिपत्य की भूमि में ही किया जावे किसी भी प्रकार के विवाद की स्थिती मे मुख्य नगर पालिका अधिकारी जिम्मेदार होंगे , तथा प्राप्त तकनीकी स्वीकृती स्वतः ही निरस्त मानी जावेगी ।
13. आर.सी.सी. नाली/नाला की स्ट्रकचरल तथा मिक्स डिजाइन का परिक्षण शासकीय पालिटेक्निक/इंजीनियरिंग कॉलेज से कराया जाकर उसका अनुमोदन अधोहस्ताक्षरकर्ता से कराया जावे । अनुमोदित डिज़ाईन अनुसार कार्य कराए जाने पर कार्य की लागत मे परिवर्तन की स्वीकृती प्राप्त करने का दायित्व निकाय के मुख्य नगर पालिका अधिकारी का रहेगा
14. म.प्र. शासन, नगरीय विकास एवं पर्यावरण विभाग मंत्रालय भोपाल के आदेश क्र. F-6-18/10/18-3/7814 भोपाल दिनांक 17 जून 2016 के अनुसार राशि रू. 1.00 लाख अथवा उससे अधिक के कराये जाने वाले कार्यो के लिये ई-टेंडरिंग व्यवस्था के माध्यम से आहुत की जाना सुनिश्चित करें।
15. कार्य के प्राक्कलन के आयटम में परिवर्तन बिना सक्षम अधिकारी के किये जाने पर परिवर्तनकर्ता निकाय तकनीकी अधिकारी/प्रशासकीय अधिकारी पर दायित्व निर्धारण होगा। निर्माण कार्य के दौरान किसी पूरक कार्य/परिवर्तन की आवश्यकता हो, तो लिखित पूर्व सूचना म0प्र0न0पा0ले0नि0 1961 नियम के प्रावधानिक प्रारुप में इस कार्यालय को देना होगी। अन्यथा पुनरीक्षित प्राक्कलन की तकनीकी स्वीकृति जारी की जाना संभव नही होगा।
16. निःशक्त जनों के लिए बाधा रहित वातावरण उपलब्ध कराया जाए। पैदल यात्रियो की सुरक्षा एवं सुरक्षित यातायात हेतु रोड सेफ्टी फीचर्स जैसे रोड साइनेज, टर्निंग प्वॉइन्ट आदि लगाये जावे।
17. नगर तथा ग्रामीण नियोजन विभाग के नियमानुसार आवश्यक स्थल अनुमोदन/अनापत्ति प्राप्त की जावे। नजूल एवं अन्य विभागों से आवश्यक एन.ओ.सी./सहमति भी प्राप्त की जावे।
18. निर्माण कार्य की लागत राशि रु. 25.00 लाख से अधिक होने पर स्थल प्रयोगशाला की स्थापना, निर्माण एजेन्सी से कराई जाकर टेस्टेड मटेरियल ही उपयोग में लाया जावे।
19. निविदा सूचना में प्रावधान किया जाये कि निविदाकार को ई.पी.एफ. एवं लेवर विभाग का पंजीयन प्रमाण पत्र देना होगा। Cost Escalation Clause लागू नहीं होगा।
20. उपरोक्त शर्तो की पूर्ति की जिम्मेदारी निकाय के मुख्य नगर पालिका अधिकारी, नगर पालिका/नगर परिषद की होगी।

अधीक्षण यंत्री / कार्यपालन यंत्री
SAGAR संभाग SAGAR

12/12

Scanned with OKEN Scanner

Project Estimate

Project Details

Project Number: PW1-375-24-016

ULB: Jatara Nagar Parishad

Department: Public Work Departme

Work : mini highmast lighting

G/L Code : 4122046005 SANITATION AND SWM SYSTEM

PAC 815,009

Total Submitted PAC(ULb):0.00

Activity / SOR / NON SOR and WBS Details

WBSN O/SNO	Activity Number	Description	Count	L	B	H	Quantity	Unit	Price / Unit	Amount	Remarks
1/1.1	NIV-13.3(7)	410 SP-20 - 8.50 METER-"SUPPLY OF STEEL TUBULAR POLE SWAGED TYPE AS PER IS:2713-1980 COMPLETE WITH BASEPLATE AND TOP CANOPY 410 SP-2 0 - 8.50 METER"	13				13.000	EA	9934.00	129142.00	
1/2.1	NIV-13.13	ERECTION OF STEEL TUBULAR OR STEEL RAIL POLE OR H-BEAM OF LENGTH EXCEEDING 8 METERS BUT NOT EXCEEDING 10 METERS IN CEMENT CONCRETE 1:3:6 (1 CEMENT : 3 COARSE SAND: 6 GRADED STONE AGGREGATE 40MM NOMINAL SIZE) FOUNDATION, BASE PADDING & MUFFING INCLUDING EXACAVATIO N AND REFILLING ETC. AS REQUIRED.(4.55 BAGS OF CEMENT/CMT.)".	13				13.000	EA	1681.00	21853.00	
1/3.1	NIV-19.10.6	150W,"-"SUPPLYING OF FLOOD LIGHT WITH HIGH POWER LED OF 1 TO3 W EACH ASSEMBLED ON SINGLE MCPCB, SYSTEM LUMENS OUTPUT WITH EFFICACY> 110 LM/W. LUMINIARE HAVING COLOR TEMP 6500K & 50000 BURNING HRS LIFE WITH MINIMUM @ L 70, THE COLOUR RENDERING INDEX OF LED LIGHT SH OULD BE MORE THAN 70. LUMINIARE COMPRISES OF DRIVER, PF 0.95 & SURGE PROTECTION 4 KV. HOUSING MADE OF PRESSURE DIE CASTALUMINIUM WIT H HEAT RESISTANT FLAT GLASS, IP66 PROTECTION.SUBMISSION LM 80-08 FORM LED SOURCE MANUFACTURER & LM79-08 / IS16106 FROM NABL APPROVED LAB. MANUFACTURER MANADATORY I/C CONNECTION LEAD, TESTING ETC TO COMPLETE THE JOB. 2 YRS GUARANTEE CERTIFICATE FROM MANUFACTURER."	52				52.000	EA	11520.00	599040.00	

Scanned with OKEN Scanner

Project Estimate

Project Details

Project Number: PW1-375-24-016
ULB: Jatara Nagar Parishad
Department: Public Work Departme

Work : mini highmast lighting
G/L Code : 4122046005 SANITATION AND SWM SYSTEM
PAC 815,009
Total Submitted PAC(ULb):0.00

Activity / SOR / NON SOR and WBS Details

WBSN O/SNO	Activity Number	Description	Count	L	B	H	Quantity	Unit	Price / Unit	Amount	Remarks
1/4.1	NIV-14.1.1(D)	10 SQ.MM.(XLPE) UNARMOURED 2 CORE-"SUPPLY OF XLPE INSULATED POWER CABLE (CONFORMING IS-7098) 1100 VOLT GRADE/HEAVY DUTY POWER CABLE CONFORMING TO IS 1554-1100 VOLTS GRADE , 2 CORE /3½ CORE/4 COREISI MARKED WITH ALU. STRANDED /SOLID CONDUCTOR UNARMOURED 2 CORE"	1	325			325.000	M	48.00	15600.00	
1/5.1	NIV-14.10(9)	LAYING OF ONE NUMBER PVC INSULATED AND PVC SHEATHED POWER CABLE OF 1.1 KV GRADE OF SIZE EXCEEDING 25 SQ.MM BUT NOT EXCEEDING 400 SQ MM IN THE EXISTING RCC/ HUME STONEWARE/G.I. PIPE AS REQUIRED."	1	325			325.000	M	26.00	8450.00	
1/6.1	NIV-13.10(A)	20X15X15CMS.-SUPPLYING AND ERECTION OF WATER TIGHT TERMINAL BOX OF 14 SWG M.S. SHEET 4MM THICK BOX OF REQUIRED SIZE TO ERECT THE SUI TABLE KIT KAT/ MCB/ SWITCH WITH TOP & BOTTOM FOLDED FITTED WITH RUBBER RING TO MAKE IT WATER TIGHT WITH POLE CLAMP MADE FROM 40X3MM M .S. FLAT IRON WITH 2 NOS. NUT AND BOLTS DULY PAINTED WITH 2 COAT OF RED OXIDE PAINT AND 2 COAT OF ALUMINIUM SILVER PAINT ERECTED WIT H CABLE GLAND BUT EXCLUDING THE COST OF THE KIT KAT/ MCB/SWITCH COMPLETE AS PER SPECIFICATION: 20X15X15CMS.	13				13.000	EA	277.00	3601.00	

Scanned with OKEN Scanner

Project Estimate

Project Details

Project Number: PW1-375-24-016

ULB: Jatara Nagar Parishad

Department: Public Work Departme

Work : mini highmast lighting

G/L Code : 4122046005 SANITATION AND SWM SYSTEM

PAC 815,009

Total Submitted PAC(ULb):0.00

Activity / SOR / NON SOR and WBS Details

WBSN O/SNO	Activity Number	Description	Count	L	B	H	Quantity	Unit	Price / Unit	Amount	Remarks
1/7.1	NIV-8.5.1(2)	6 AMP TO 32 AMP RATING-"SUPPLYING OF ISI MARKED AND ACCEPTED STANDARD OF MINIATURE CIRCUIT BREAKER (MCB) OF 'C' SERIES SUITABLE FOR 240/415 VOLTS, 50 CYCLE , 10 KA VALUE AC SUPPLY CONFIRMING TO IS : 8828 : 1996, IEC : 60898 :2002 BUT WITHOUT ENCLOSURES :- SINGLE P OLE (SP)"	26				26.000	EA	81.00	2106.00	
1/8.1	EM103522022NS R979	PWD SOR(Item No42.109)Ring carriage dia Providing and fixing of ring carriage dia. not less than 750mm made of 50mm dia. GI pipe Light 'A' class for 70mm A/F top octagonal pole with required clamps, nut, bolt etc as required.	13				13.000	EA	2468.00	32084.00	
1/9.1	NIV-15.13	SUPPLYING, INSTALLING, TESTING OF EARTH COIL (COIL OF 115 TURNS OF 50MM DIA, AND 2.5 MTRS. LEAD OF 4 MM G.I WIRE."	13				13.000	EA	241.00	3133.00	

Scanned with OKEN Scanner

Project Estimate

Project Details

Project Number: PW1-375-24-016
ULB: Jatara Nagar Parishad
Department: Public Work Departme

Work : mini highmast lighting
G/L Code : 4122046005 SANITATION AND SWM SYSTEM
PAC 815,009
Total Submitted PAC(ULb):0.00

Activity / SOR / NON SOR and WBS Details

SNO	WBS NO	WBS Text	Amount
1	PW1-375-24-016.001	mini highmast lighting	815009.00
		Total PAC	815009.00

Created by (Sub eng / A.E) and digitally signed by	IST : 12:00:00 AM
Forwarded by (CMO / Comm) and digitally signed by	IST: 12:00:00 AM

GST 146,701.62
Gross 961,710.62

TECHNICAL SANCTION AS PER CONDITIONS,VIDE, Notification -
Dated : 2024-12-12
For Construction of : mini highmast lighting

At ward No : 1 **Gross Granted for RS** : 961710.62
In Words : NINE LAKH SIXTY ONE THOUSAND SEVEN HUNDRED TEN Rupees SIXTY TWO Paise

GST is 18% applicable on this project, Amount - 146701.62
Checked by :Sub.Eng. / A.E(optional)

Checked by (Sub eng and digitally signed	IST:-12:00:00 AM	Checked by A.E and digitally signed	IST: - 12:00:00 AM

Note:

Assistant / Executive / Superintendent Engineer
Urban Administration & Development, Sagar Division

A.E/ E.E/ S.E: Megh Tiwari — Digitally signed by Megh Tiwari Date: 2024.12.13 14:17:47 +05'30'

S.E

Scan to Verify TS

Important Note: Valid only after digital signature of CMO/Commissioner and EE

Scanned with OKEN Scanner

Mandatory documents required from bidder:

- Bidder should have given the undertaking on letterhead with seal and sign that products should supply and install on locations.
- Bidder should have submitted income tax return last 3 years
- Bidder should be registered in the local state of bid inviting authority which should be carried along with GST registration, Pan Cards. Bidder should not be bankrupt, court receivership or similar proceedings, debarred or black list under taking must be uploaded with bid on stamp.
- The Bidder is expected to go through the tender document carefully to understand the documents required to be examine all instructions, forms, terms, specifications and annexure in the Bidding Documents. Failure to furnish all information required by the Bidding Documents or submission of a bid not substantially responsive to the Bidding Documents in every respect will be at the Bidder's risk and may result in rejection of bid.
- Each page of the documents including specifications must be authenticated by using official seal and signature of authorized signatory of the bidder.
- Technical Bid will be opened first and will be evaluated as per specification and terms &conditions. Thereafter, Price Bid will be opened only for those bidders whose bid is found technically qualified.
- EMD exemption not allowed.
- Led Lights must be branded Havells, Syska, Surya, and Bajaj.
- Bidder should submit EMD (9617) in FDR format in favour of **CMO Nagar Parishad JATARA** and also submit hard copy of EMD before bid end date.